Worth Construction

PLUMBING TAKEOFF PACKAGE

WP-1001 | Sample fourplex
Sample Owner LLC | Rev A | 11/2/2026

Takeoff Summary

BUILDING TYPE
Residential (private use)

PROJECT TYPE
New

FIXTURES
34

TOTAL DFU
48

TOTAL WSFU (COLD / HOT / TOTAL)
28.8 / 19.6 / 40

EST. PEAK DEMAND
26.3 gpm

MIN. BUILDING DRAIN @ 1/4"/FT
4"

LARGEST SANITARY ENTERED
4"

LABOR HOURS
243.89

MATERIAL (EXCL. FIXTURES)
$9,122.00

FIXTURES FURNISHED BY WORTH
$11,200.00

ESTIMATED TOTAL
$58,465.92

Review items

[WARNING] Unit A - Bath Lavatory: Drain stub height measured 21", expected 16" to 20". Confirm against the fixture cut sheet before setting the fixture. Re-rough if it does not fit.

Notes

Sample job: typical unit entered once and multiplied by 4.

Basis

Fixture units and sizing are code-default references (IPC) for estimating only. Confirm against the approved plans, fixture cut sheets, and the adopted code edition. Sizing shown here is not an engineered design.

Fixture Schedule

AREA	FIXTURE	QTY / AREA	X AREAS	TOTAL	FURNISHED	DFU	WSFU C/H/T
Unit A - Bath	Water closet, tank type	1	4	4	Worth	12	8.8 / 0 / 8.8
Unit A - Bath	Lavatory	1	4	4	Worth	4	2 / 2 / 2.8
Unit A - Bath	Bathtub / tub-shower	1	4	4	Worth	8	4 / 4 / 5.6
Unit A - Kitchen / Laundry	Kitchen sink	1	4	4	Worth	8	4 / 4 / 5.6
Unit A - Kitchen / Laundry	Dishwasher connection	1	4	4	Others	8	0 / 5.6 / 5.6
Unit A - Kitchen / Laundry	Ice maker / refrigerator box	1	4	4	Others	0	1 / 0 / 1
Unit A - Kitchen / Laundry	Clothes washer outlet box	1	4	4	Others	8	4 / 4 / 5.6
Unit A - Kitchen / Laundry	Water heater, electric tank 50 gal	1	4	4	Worth	0	0 / 0 / 0
Exterior	Hose bibb, frost-free	2	1	2	Worth	0	5 / 0 / 5
Total				**34**		**48**	**28.8 / 19.6 / 40**

Material Takeoff

Underground

GROUP	DESCRIPTION	UNIT	QTY	ORDER	ORDER NOTE	EXT. COST	LABOR HR
Pipe	PEX-A (coil) 1-1/4" pipe	lf	60	100	1 x 100' coil (incl. 10% waste)	$360.00	2.4
Pipe	PVC Sch 40 DWV 3" pipe	lf	112	140	7 x 20' sticks (incl. 10% waste)	$406.00	10.08
Pipe	PVC Sch 40 DWV 4" pipe	lf	85	100	5 x 20' sticks (incl. 10% waste)	$410.00	9.35
Fittings	PEX-A (coil) 1-1/4" fittings (avg)	ea	14	14		$308.00	2.1
Fittings	PVC Sch 40 DWV 3" fittings (avg)	ea	24	24		$192.00	7.92
Fittings	PVC Sch 40 DWV 4" fittings (avg)	ea	16	16		$224.00	6.4
Underground total						**$1,900.00**	**38.25**

Rough-in

GROUP	DESCRIPTION	UNIT	QTY	ORDER	ORDER NOTE	EXT. COST	LABOR HR
Rough-in kits	1-1/2" DWV P-trap	ea	4	4		$36.00	0
Rough-in kits	1-1/2" san-tee & trap adapter stub	ea	8	8		$72.00	0
Rough-in kits	1/2" drop-ear elbow	ea	8	8		$56.00	0
Rough-in kits	1/2" supply stub-out w/ test cap	ea	24	24		$156.00	0
Rough-in kits	3/4" ball valve	ea	4	4		$72.00	0
Rough-in kits	Closet flange 3x4 PVC	ea	4	4		$72.00	0
Rough-in kits	Frost-free hose bibb w/ vacuum breaker	ea	2	2		$96.00	0
Rough-in kits	Ice maker outlet box	ea	4	4		$140.00	0
Rough-in kits	Pressure-balance valve body (rough)	ea	4	4		$480.00	0
Rough-in kits	Stub-out bracket	ea	4	4		$16.00	0
Rough-in kits	Tub waste & overflow	ea	4	4		$260.00	0
Rough-in kits	Washer outlet box w/ valves	ea	4	4		$220.00	0
Rough-in kits	Water hammer arrestor	ea	8	8		$176.00	0
Rough-in kits	Water heater drain pan	ea	4	4		$120.00	0
Pipe	PEX-A (coil) 1/2" pipe	lf	440	500	5 x 100' coils (incl. 10% waste)	$375.00	11
Pipe	PEX-A (coil) 3/4" pipe	lf	280	400	4 x 100' coils (incl. 10% waste)	$500.00	8.4
Pipe	PVC Sch 40 DWV 1-1/2" pipe	lf	80	100	5 x 20' sticks (incl. 10% waste)	$110.00	4.8
Pipe	PVC Sch 40 DWV 2" pipe	lf	232	260	13 x 20' sticks (incl. 10% waste)	$377.00	16.24
Fittings	PEX-A (coil) 1/2" fittings (avg)	ea	100	100		$450.00	8
Fittings	PEX-A (coil) 3/4" fittings (avg)	ea	64	64		$448.00	6.4

Material Takeoff (cont.)

GROUP	DESCRIPTION	UNIT	QTY	ORDER	ORDER NOTE	EXT. COST	LABOR HR
Fittings	PVC Sch 40 DWV 1-1/2" fittings (avg)	ea	12	12		$30.00	2.4
Fittings	PVC Sch 40 DWV 2" fittings (avg)	ea	40	40		$140.00	10
Hangers & supports	Hanger / strap, plastic pipe	ea	80	80		$280.00	12
Hangers & supports	PEX clip / strap	ea	276	276		$276.00	13.8
Insulation	Pipe insulation, 1/2" wall for 1/2" pipe	lf	200	200		$550.00	6
Insulation	Pipe insulation, 1/2" wall for 3/4" pipe	lf	120	120		$330.00	3.6
Rough-in total						**$5,838.00**	**102.64**

Set & trim

GROUP	DESCRIPTION	UNIT	QTY	ORDER	ORDER NOTE	EXT. COST	LABOR HR
Fixtures & equipment	Bathtub / tub-shower	ea	4	4		$2,600.00	0
Fixtures & equipment	Clothes washer outlet box (furnished by others)	ea	4	4	Install only	$0.00	0
Fixtures & equipment	Dishwasher connection (furnished by others)	ea	4	4	Install only	$0.00	0
Fixtures & equipment	Hose bibb, frost-free	ea	2	2		$0.00	0
Fixtures & equipment	Ice maker / refrigerator box (furnished by others)	ea	4	4	Install only	$0.00	0
Fixtures & equipment	Kitchen sink	ea	4	4		$1,800.00	0
Fixtures & equipment	Lavatory	ea	4	4		$1,100.00	0
Fixtures & equipment	Water closet, tank type	ea	4	4		$1,300.00	0
Fixtures & equipment	Water heater, electric tank 50 gal	ea	4	4		$4,400.00	0
Trim kits	1-1/2" P-trap kit (sink)	ea	4	4		$64.00	0
Trim kits	1-1/4" P-trap kit (lav)	ea	4	4		$56.00	0
Trim kits	1/2" x 3/8" quarter-turn angle stop	ea	20	20		$240.00	0
Trim kits	3/8" braided faucet supply	ea	16	16		$144.00	0
Trim kits	Braided toilet supply	ea	4	4		$36.00	0
Trim kits	Dishwasher supply & 90 elbow	ea	4	4		$88.00	0
Trim kits	Double-bowl continuous waste	ea	4	4		$72.00	0
Trim kits	Escutcheon	ea	28	28		$56.00	0
Trim kits	Ice maker supply line	ea	4	4		$72.00	0
Trim kits	Sealant / setting consumables	ea	4	4		$32.00	0
Trim kits	T&P discharge piping	ea	4	4		$100.00	0
Trim kits	Thermal expansion tank	ea	4	4		$260.00	0

Material Takeoff (cont.)

GROUP	DESCRIPTION	UNIT	QTY	ORDER	ORDER NOTE	EXT. COST	LABOR HR
Trim kits	Water heater connector	ea	8	8		$128.00	0
Trim kits	Wax ring & closet bolts	ea	4	4		$36.00	0
Set & trim total						**$12,584.00**	**0**

Fixture labor

PHASE	DESCRIPTION	QTY	LABOR HR
Rough-in	Bathtub / tub-shower - rough-in	4	14
Rough-in	Clothes washer outlet box - rough-in	4	6
Rough-in	Dishwasher connection - rough-in	4	2
Rough-in	Hose bibb, frost-free - rough-in	2	2
Rough-in	Ice maker / refrigerator box - rough-in	4	3
Rough-in	Kitchen sink - rough-in	4	6
Rough-in	Lavatory - rough-in	4	6
Rough-in	Water closet, tank type - rough-in	4	8
Rough-in	Water heater, electric tank 50 gal - rough-in	4	6
Set & trim	Bathtub / tub-shower - set & trim	4	6
Set & trim	Clothes washer outlet box - set & trim	4	1
Set & trim	Dishwasher connection - set & trim	4	4
Set & trim	Hose bibb, frost-free - set & trim	2	0.5
Set & trim	Ice maker / refrigerator box - set & trim	4	1
Set & trim	Kitchen sink - set & trim	4	6
Set & trim	Lavatory - set & trim	4	5
Set & trim	Water closet, tank type - set & trim	4	4
Set & trim	Water heater, electric tank 50 gal - set & trim	4	10

Pipe Run Summary

SYSTEM	MATERIAL	SIZE	LOCATION	LENGTH (FT)	FITTINGS	HANGERS
Domestic cold water	PEX-A (coil)	1-1/4"	Underground	60	14	0
Domestic cold water	PEX-A (coil)	3/4"	Aboveground	160	36	60
Domestic cold water	PEX-A (coil)	1/2"	In Wall	240	56	92
Domestic hot water	PEX-A (coil)	3/4"	Aboveground	120	28	48
Domestic hot water	PEX-A (coil)	1/2"	In Wall	200	44	76
Sanitary / waste	PVC Sch 40 DWV	4"	Underground	85	16	0
Sanitary / waste	PVC Sch 40 DWV	3"	Underground	112	24	0
Sanitary / waste	PVC Sch 40 DWV	2"	In Wall	72	16	20
Vent	PVC Sch 40 DWV	2"	Aboveground	160	24	40
Vent	PVC Sch 40 DWV	1-1/2"	In Wall	80	12	20

Rough-In Field Verification

AREA	FIXTURE	DIMENSION	MEASURED	TARGET	RANGE	STATUS
Unit A - Bath	Water closet, tank type	Drain CL from finished wall	12-1/4"	12"	11-1/2" - 12-1/2"	OK
Unit A - Bath	Lavatory	Drain stub height	21"	18"	16" - 20"	OUT OF RANGE
Unit A - Bath	Bathtub / tub-shower	Valve CL height	28-1/2"	28"	26" - 34"	OK

Ranges are typical rough-in values from the Worth fixture library. The approved fixture cut sheet governs.